

# Graincorp Liquid Terminals

Hawkins Group was engaged as principal contractor to manage and undertake the civil package at Graincorp's new liquid storage facility at Pinkenba, Qld.

The project included 1000lm of cast in-situ 3m high concrete bund walls, one kilometre of ring road and associated drainage. Also included was the supply and installation of approximately 22,000m<sup>2</sup> of HDPE liner for spill containment.

Hawkins undertook the management of sub-contractors including electrical and pipe installers as part of the charter.

Hawkins Group worked closely with the client Graincorp and consultants NDHA to complete the project safely and on schedule.

**Client:**  
Graincorp

**Location:**  
Pinkenba, QLD

**Contract type:**  
Lump sum Contract

**Completed:**  
2015

General construction 

